

British Standards Institute publication

Trees in relation to construction – Recommendations [BS5837:2005]

and the British Standards Institute (BSI) (BS) publication Guide for Trees in Relation to Construction [BS 5837:1991]

Matheny N., and Clark J., Trees and Development: A Technical Guide to the preservation of Trees During Land Development, International Society of Arboriculture, 1998 pp183

Terms used are different for the ISA and BS but essentially the planning and arboricultural processes are the same.

ARBÔREA

Arboricultural processes are divided into 9 elements

1. Perform a tree stand delineation

- 2. Tree survey within development area
- 3. Identify trees suitable for preservation
- 4. Access the potential impacts to trees
- 5. Suggest modifications to development plans
- 6. Identify tree work required prior to clearing and grading or predevelopment works
- 7. Prepare specification for tree preservation
- 8. Monitor trees during construction
- 9. Prepare a post-construction maintenance plan

Overview: Primary aim of tree preservation

Long-term survival and stability of the trees(s).

The International Society of Arboriculture (ISA) identifies three main principles:

1. Tree preservation programs must respect pattern of tree growth and development

2. Preservation must focus on preventing injury to trees

3. Tree preservation requires space

ARBÔREA

Arboricultural processes are divided into 9 elements

- 1. Perform a tree stand delineation
- 2. Tree survey within development area
- 3. Identify trees suitable for preservation
- 4. Access the potential impacts to trees
- 5. Suggest modifications to development plans
- 6. Identify tree work required prior to clearing and grading or predevelopment works
- 7. Prepare specification for tree preservation
- 8. Monitor trees during construction
- 9. Prepare a post-construction maintenance plan

ARBÔREA

Arboricultural Implications Assessment (AIA)

Syn: ISA-Tree Protection Plan

Study undertaken by an arboriculturalist, to: - identify, evaluate and possibly mitigate the extent of direct and indirect impacts on existing trees - especially those impacts that may arise as a result of the implementation of any site isyout proposal.

ISA includes this within the written tree protection plan; typically a written report (as above)


Arboricultural Method Statement (AMS)

Syn: ISA-Tree Protection Plan, Specifications

Methodology for the implementation of any aspect of development that has the potential to result in loss of or damage to a tree.

ISA, in general terms, includes this in its *specifications* and does not require methodology be detailed for each tree.

- It is recommended that the BS AMS be adopted for the ISA tree protection plan (written spec., or method statement in report appendix).





Typical Symptoms of Tree Stress From
Construction InjuryAttack by borers and other stress
related pestsShort seasonal growth elongation
Small leaves [often yellow]Attack by borers and other stress
related pestsThin foliage density
Leaf scorchHarry sed mast productionWitting
Epicomic shootsHeavy seed mast productionTwig and branch diebackHeavy seed mast production

ga Western red cedar Thuja plicata d Poor - Moderate Relative species tolerance
d Relative species
torerance
Response is very init site dependant and probably related to soil moisture. WT offerant of root ddition pruning. Intolerant of fill (grading). f poor e to s s



Condition Rating	Overall Vigor	Canopy Density	Amount of Deadwood	History of Failure	Pests	Extent of Decay
1	Severe Decline	<20%	Large; major scaffold branches/primary	More than one scaffold/primary	Infested	Major - conk and cavaties
2	Declining	20-60%	Twig and branch dieback/tertiary and primary	Scaffold branches/ primary	Infestation of significant pests	One to a few conks; smal cavaties
3	Low/Moderate	60-90%	Small twigs/tertiary	Small branches/ secondary	Minor	Present at pruning wounds
4	Good	90-100%	Little or none	None	Minor	Present at pruning wounds
5	Excellent	100%	None	None	None or insignificant	Absent



Tree Survey: Post-Planning

This is where an arboricultural assessment is not obtained until after a preliminary site layout has been prepared.

Although this is not the ideal situation, timely and appropriate expert advice can still make valuable contributions to the process of tree retention and protection.

In cases where the arborist is provided a layout, the tree survey should be completed as detailed in the Tree Survey section.

This would then involve providing advice on tree retention, protection, remedial or mitigation works and new landscape design.

It is essential that the trees be assessed objectively and without reference to site layout proposals.

This is covered under the Arboricultural Implications Assessment (AIA) and Design Issues.

ARBÔREA

Tree Constraints Plan

The influence trees have on the site layout design is plotted on the Tree Constraints Plan (TCP).

This illustrates both above ground owing to their size and position
 and the underground constraints due to the Root Protection Area (RPA).

The RPA is presented separately as it is a new method of determining the soil and root area to be protected.

Critical Factors in Evaluating Tolerance to Construction Impact

 The likely tolerance of any form of tree to root disturbance or damage. This is based on factors such as species, age and condition and presence of other trees. (For individual open grown trees, it may acceptable to offset the distance by up to 20% in one direction

 The morphology and disposition of the roots, when known to be influenced by past or existing site conditions e.g. the presence of roads, structures and underground services

- The soil type and structure
- Topography and drainage

 Where any significant part of the trees' crown overhangs the provisional position of the tree protection barriers, these parts may sustain damage during the construction period

In such cases, it may be necessary to increase the extent of tree protection barriers to contain and thereby protect the spread of the crown.

Protection may also be achieved by access facilitation pruning.

The arborist determines all this.

ARBÔREA

Arboricultural Implications Assessment (AIA) and Design Issues

The tree constraints plan, discussed previously, is utilised in the design layout. It should however be taken in context as trees are only one factor requiring consideration in this regard.


Important and sensitive trees may prevent development or dramatically alter its design.

Retention of unsuitable trees, or too many, should be removed from consideration so as to avoid excessive pressure on trees during development and subsequent demands for their removal.


NOTE: Trees are material considerations in the formal planning system, whether or not they are statutorily/legally protected

ARBÔREA

Clearing and grading works



















Clearing and grading works					
Activity	Impact	Methods/treatments to minimise damage			
Trenching for utilities, stormwater system, drains	Root loss	- Avoid open trenching in rooting area - Tunnel under roots, if possible. If not, within root area, dig trench by hand, bridging roots greater than 1 inches / 254 mm - Consolidate utilities into one trench			
Compacted surface soils	Unfavourable conditions for root growth; chronic stress from reduced root systems	Fence trees to keep traffic and storage out of root area Provide a storage area and traffic route/area for construction activity away from trees Where traffic cannot be diverted, protect soil surface			



Clearing and	grading works	
Tree diameter	Auger / Trenchless distance from tree	
5-9 inches	5 feet	
10-14 inches	10 feet	
15-19 inches	12 feet	
over 19 inches	15 feet	
ARBI	Monum 1.0 m 1.0 m	1.0 m / 3.2 feet











ISA - Tree Protection Zone / Root Protection Area					
Species Tolerance	Tree Age	Distance from trunk feet per inch trunk diameter			
Good	Young (<20% life expectancy) Mature (20-80% life expectancy) Overmature (>80% life expectancy)	0.5 feet 0.75 feet 1 foot			
Moderate	Young Mature Overmature	0.75 feet 1 loot 1.25 feet			
Poor	Young Mature Overmature	1 foot 1.25 feet 1.5 feet			
	ARBÔ	REA			














ARBÔREA

 Inset encoded to a protection acone that covers the trees optimum rooting zone
 should be of substantial construction i.e. plywood, chain-link or sheet metal fence fines and penalties for violating
the

area demarcated by the barrier. This can either be included in the contract or specifications • location of the barrier is determined by the certified arborist based on species tolerance, condition, and age the barrier placement should also account for working space


ISA - Tree Protection Zone

Tree Protection Barriers


10/31/2014



















Must include an assessment on the health and structure of the tree(s); Risk Assessment In addition the following should also be addressed:

destruction of the general root system, particularly
 dealage to branches
 dealage to branches

· damage to the root collar and structural roots obstructions mechanical injury and damage to the stem

decline in overall health

 changes in soil structure such as compaction, fill(s), erosion, and loss of organic matter changes in wind loading in the crown, which is
particularly related to potential for failure

ARBÔREA

Other Post-Construction Requirements

The amount of water applied must be appropriate to the species requirement

Light, frequent irrigation's should be avoided. Irrigation should wet the entire root zone and be allowed to dry before another application

Excess irrigation from new landscapes should be avoided.
 Runoff from plantings should be minimised and or directed away from trees

· Wetting the trunk should be avoided

Pruning

Irrigation

 Annual inspection of retained trees is required. Prescribed treatments are typically based on the results of inspection Pruning to mitigate risk is the priority following construction impacts

Mulching

 See section on mulching previously Application of 100 – 150 mm / 4 - 6 inches of mulch is recommended to the edge of the drip line or Tree Protection Zone, which ever is greatest


Mulch should be kept away from the trunk base

Fertilisation


An assessment of the soil nutrient content is preferred prior to any application so that specific nutrient deficiencies can be targeted

Application of a balanced slow release, low concentration, fertiliser is recommended











The entire root system is typically concentrated within the uppermost 910 $\,\rm mm$ / 36 inches of the soil:

 although it may be deeper within the dense mass of roots and soil close to the trunk and in sinker roots
 within a short distance the root system branches, forming a network of small diameter woody roots, that typically extend radially for a distance much further than the height of the tree
 this is except where impeded by unfavourable conditions

All parts of this system bear a mass of fine absorbing roots (non-woody / soft tissue).

Absorbing root system within the top 450 mm / 18 inches

ARBÔREA

Any excavations that encounter roots over 25 mm / 1 inch diameter requires particular care be used to avoid damage; hand excavation is usually prescribed, avoiding damage to the bark.

Other methods of excavation are now available i.e. hydro or pneumatic excavation.

Roots exposed should be surrounded by sharp (washed) sand before replacing soil or other material in the excavation area.

ARBÔREA

Indirect (and Direct) Damage to Roots


Tree roots develop in the soil at a level where oxygen and moisture are available in the appropriate concentrations.

Sudden alteration of the depth of soil over roots as a result of lowering (Direct) or raising the soil level within the branch spread or area designated as critical to the survival of the tree can kill the roots and as a result the tree may die.






















Risk Rating for Root Loss and or Root Decay

Critical Risk: >50% of roots with significant decay / loss, or if affected roots is uphill or opposite lean High Risk: >33% of roots with significant decay / loss, or if affected roots is uphill or opposite lean

Moderate Risk: <33% of roots with some decay or cut Low Risk: no decay or cut roots, not in low or wet site and so on

ARBÔREA

ARBOREA CONSULTANTS, LLC